

PLUMBING CAMERA WORK

Commercial.

Ran the camera through a total of five outside clean outs and a total of three separated, cast-iron lines inside of a hatchway in the main building. And was able to get under the old cafeteria and the building to the west of the gym. The building to the west of the gym has back fall on some of the sewer lines and has pressure fittings and some of them as well. When we ran the camera through one clean out outside on the west side of the gym, it is an old clay pipe, and the line has multiple brakes and rocks and mud and is unable to go more than 10 to 15 foot either direction.

The four cleanouts on the main building in the courtyard the pipes are holding water and has rocks and other debris in them. and one line we were able to go approximately 20 foot but could not go any further due to roots in the line.

The Ground floor of the main building I recommend pulling multiple toilets in different locations and running the camera through them to inspect the sewer line under the building itself since we could not get anything to go from the cleanouts in the courtyard under the building.

(note)

Need to verify where the city tap for the sewer is located.



















